



ADDENDUM No. 1
To the
RFP DOCUMENTS
for
District of Elkford
Highway 43 Trail Construction and Improvements
RFP No. 2017.05

To All Bidders:

The following change, additions, and/or deletions are hereby made part of the Invitation to Request for Proposal documents for "Highway 43 Trail Construction and Improvements" and completely as if the same were fully set forth therein.

NOTE TO BIDDERS:

Include a price to use 3-Inch Minus for the Sub-Base supplied by the District of Elkford at a pit 3 km (one way) from the job site, but do not total the price into the total price of the contracts. All work to be the same except the purchase of gravel. Trucking and loading to be completed by contractor.

Please see the following schedule of quantities on the following page.

Specification Title	Unit	Quantity	Unit Price	Amount
Granular Sub-Base 3-Inch Minus 150mm Thickness for Trails - Compacted Option 1: (Contractor to provide material)	Square Metres	5610		
Granular Sub-Base 3-Inch Minus 150mm Thickness for Trails – Compacted Option 2: (District supplied material (Pit 3 km one way trip from midpoint of project), contractor to haul and load)	Square Metres	5610	*excluding supplied gravel price	
Removal and Disposal of Unsuitable Subgrade Top soil and organic materials to be stripped 150mm in depth (excavation can stop once suitable natural gravel is reached is reached)	Square Metres	5610		
Granular Sub-Base 3-Inch Minus 300mm Thickness for Trails - Compacted Option 1: (Contractor to provide material)	Square Metres	2760		
Granular Sub-Base 3-Inch Minus 300mm Thickness for Trails – Compacted Option 2: (District supplied material (Pit 3 km one way trip from midpoint of project), contractor to haul and load)	Square Metres	2760	*excluding supplied gravel price	
Removal and Disposal of Unsuitable Subgrade Top soil and organic materials to be stripped 150mm in depth (excavation can stop once suitable natural gravel is reached is reached)	Square Metres	2760		
Filter Fabric Filter fabric to be placed between existing ground and sub-grade if existing ground is prone to ground water or is not suitable	Square Metres	1380		
Granular Base 3/4 Inch 150mm Thickness for Trails – Compacted	Square Metres	7875		
Boardwalk Construction of simple 3m wide Boardwalk	Lineal Metres			
Bridges Construction of simple 3m wide bridge less than 5 m in length				
Culverts Installation of 300 mm culverts less than 5 m in length				

Although the District expects that this will be a suitable estimate of quantities, quantities of actual work completed will be paid. Where option 1 and 2 are noted, only one will be selected and completed/paid

All Bidders shall acknowledge receipt and acceptance of this Addendum by signing in the space provided and submitting the signed Addendum with the bid. Bids submitted without this Addendum may be considered incomplete.

Yours truly,
District of Elkford

Scott Beeching
Director, Planning and Development Services

Receipt acknowledged and conditions agreed to this _____ day of _____, 2017.

Bidder

Signature